



| GENERAL INFORMATION   |  |  |   |  |          |
|---|--|--|---|--|----------|
| Total power, kWp_DC   |  |  |   |  | 9987     |
| Total power, kWp_AC   |  |  |   |  | 8400     |
| Nominal power (CEI 0-16, see 2E100 for details - sum of minor between AC and DC on each inverter) |  |  |   |  |          |
|   |  |  |   |  |          |
| Module power, Wp_DC   |  |  |   |  | 660      |
| Module quantity   |  |  |   |  | 15132    |
| Azimut  |  |  |   |  | 0        |
| Modules manufacturer/ model   |  |  | Hi-Mo 9/ LR8-66HYD_635-660M                                 |  |          |
| Inverter manufacturer/ model  |  |  | Huawei // SUN2000-330KTL-H1                                 |  |          |
| Inverters nominal AC power, kW_AC   |  |  |   |  | 300      |
| Inverters n.  |  |  |   |  | 28       |
| Capacity, kW_AC   |  |  |   |  | 8400     |
| Cadastral data  |  |  | Forlì - Fg. 225 Mapp. 49, 662, 1612, 1613, 1691, 1693, 1700 |  |          |
| Road lenght, m  |  |  |   |  | 1941,994 |
| Road Width, m   |  |  |   |  | 4        |
| Fence length, m   |  |  |   |  | 1846,09  |
| Mitigation length, m  |  |  | 2029,951  |  |          |
| Mitigations, m2   |  |  | 1623,918  |  |          |

| DATI IMPIANTO |                       |                          |                  |                   |                        |
|---------------|-----------------------|--------------------------|------------------|-------------------|------------------------|
| NOME IMPIANTO | POTENZA DI PICCO [MW] | POTENZA DI MODULO FV [W] | QUANTITA' MODULI | QUANTITA' TRACKER | DISTANZA INTERFILA [m] |
| IMPIANTO      | 9,98712               | 660                      | 15132            | 582               | 5                      |
|               |                       |                          |                  |                   |                        |
| <b>TOTALE</b> | <b>9,99</b>           | -                        | <b>15132</b>     | <b>582</b>        | -                      |

## LEGENDA

-  CONFINE MAPPALE
-  FASCE DI MITIGAZIONE SIEPE PERIMETRALE
-  FASCIA DI MITIGAZIONE ALBERATA
-  RECINZIONE
-  VIABILITA' INTERNA
-  TRACKER (26 MODULI)
-  1/2 TRACKER (13 MODULI)
-  CABINE DI UTENTE
-  CABINA DI CONSEGNA IN PROGETTO
-  INVERTER
-  ACQUEDOTTO ROMAGNA ACQUE E FASCIA DI RISPETTO
-  LIMITE STRADA E FASCIA DI RISPETTO STRADALE
-  IPOTESI COLLEGAMENTO ELETTRICO TRA CABINE

# IMPIANTO AGROFOTOTRAICO "FORLÌ"

---

REGIONE EMILIA ROMAGNA  
COMUNE DI FORLÌ<sup>1</sup>  
PROVINCIA DI FORLÌ-CESENZA

---

PROCEDURA ABILITATIVA SEMPLIFICATA (P.A.S.)  
art. 8 Testo Unico EER DI n. 190/2024

---

Elaborato:  
3.03 - Planimetria generale impianto\_AGG1  
Formato A/0

Committente:

---

Progettisti: